

YORK STREET INTERCHANGE

OPTION B



Legend

M2 — Westlink
Westlink — M2
M3 — Westlink
Westlink/Dock Street — M3
York Street (Northbound)
York Street — M2

Key Features :

- Movement between M2 and Westlink via new bridge over existing Lagan Road and Dargan Rail bridges, approximately 18m above existing ground level.
- Movement between Westlink and M2 via underpass below existing ground level under new York Street bridge and existing Dargan Rail bridge.
- Westlink to M3 movement via underpass below existing ground level and under new York Street bridge.
- M3 to Westlink movement via new bridge over York Street.
- All slip roads at Clifton Street remain open.
- Cost approximately £100m.